

TEST REPORT

Date: March 26, 2010

Company: Nawoo Tech Ltd

We hereby certify that samples of the material identified below by batch number, have been analyzed in accordance with test methods that meet and/or exceed the detection limits for fluoride, chloride, and sulfur per ASME Boiler and Pressure Vessel Code, Section V, Article 6, paragraph T-641, 1998-2008 Editions and Addenda with the following results:

SAMPLE		RESIDUE	FLUORIDE	CHLORIDE	SULFUR
PICO COLOR CHECK	NPR1-3	0.0206 G	<0.0003%BW	<0.0002%BW	<0.0003%BW
REMOVER BATCH NO.	10NPR11				

SHERWIN INCORPORATED

Robert Siegel Laboratory Director

