

TEST REPORT

Date: March 25, 2013

Company: Nawoo Tech Ltd

Test Report NP23

We hereby certify that samples of the material identified below by batch number, have been analyzed in accordance with test methods that meet and/or exceed the detection limits for fluoride, chloride, and sulfur per ASME Boiler and Pressure Vessel Code, Section V, Article 6, paragraph T-641, 1998-2011 Editions and Addenda with the following results:

| SAMPLE | | RESIDUE | FLUORIDE | CHLORIDE | SULFUR |
|------------|---------|-----------|------------|------------|------------|
| PICO COLOR | NPW-2 | 13.2069 G | <0.0001%BW | <0.0002%BW | <0.0002%BW |
| CHECK | | | | | |
| PENETRANT | | | | | |
| BATCH NO. | 13NPW14 | | | | |

SHERWIN INCORPORATED**Robert Siegel**
Laboratory Director