

TEST REPORT


Date: Match 26, 2010

Company: Nawoo Tech Ltd

We hereby certify that samples of the material identified below by batch number, have been analyzed in accordance with test methods that meet and/or exceed the detection limits for fluoride, chloride, and sulfur per ASME Boiler and Pressure Vessel Code, Section V, Article 6, paragraph T-641, 1998-2008 Editions and Addenda with the following results:

SAMPLE		RESIDUE	FLUORIDE	CHLORIDE	SULFUR
PICO COLOR	NPP-2	1.8504 G	<0.0002%BW	<0.0002%BW	<0.0004%BW
CHECK					
PENETRANT					
BATCH NO.	10NPP11				

SHERWIN INCORPORATED

Robert Siegel
Laboratory Director