

TEST REPORT

Date: March 20, 2015

Company: Nawoo Ltd

Test Report ND5

We hereby certify that samples of the material identified below by batch number, have been analyzed in accordance with test methods that meet and/or exceed the detection limits for fluoride, chloride, and sulfur per ASME Boiler and Pressure Vessel Code, Section V, Article 6, paragraph T-641, 1998-2013 Editions and Addenda with the following results:

SAMPLE		RESIDUE	FLUORIDE	CHLORIDE	SULFUR
PICO COLOR	NPD-4	14.6196	<0.0014%BW	<0.0020%BW	<0.0014%BW
CHECK					
DEVELOPER					
BATCH NO.	15NPD16				

SHERWIN INCORPORATED
Robert Siegel
Laboratory Director