

TEST REPORT

Date: April 15, 2020

Company: Nawoo Ltd

Test Report ND00

We hereby certify that samples of the material identified below by batch number, have been analyzed in accordance with test methods that meet and/or exceed the detection limits for fluoride, chloride, and sulfur per ASME Boiler and Pressure Vessel Code, Section V, Article 6, paragraph T-641, 1998-2019 Editions and Addenda, and SE-165 with the following results:

SAMPLE	RESIDUE	FLUORIDE	CHLORIDE	SULFUR
PICO COLOR CHECK DEVELOPER BATCH NO.	NPD-4 20NPD21	10.5789G <0.0001%BW	<0.0001%BW <0.0001%BW	<0.0001%BW <0.0001%BW

SHERWIN INCORPORATED



Robert Siegel
Laboratory Director