

TEST REPORT

Date: March 13, 2019

Company: Nawoo Ltd

Test Report NP29

We hereby certify that samples of the material identified below by batch number, have been analyzed in accordance with test methods that meet and/or exceed the detection limits for fluoride, chloride, and sulfur per ASME Boiler and Pressure Vessel Code, Section V, Article 6, paragraph T-641, 1998-2017 Editions and Addenda with the following results:

| SAMPLE | | RESIDUE | FLUORIDE | CHLORIDE | SULFUR |
|--------------------------------------|------------------|----------|------------|------------|------------|
| PICO COLOR CHECK PENETRANT BATCH NO. | NPW-2 19NPW20 | 64.5671G | <0.0001%BW | <0.0001%BW | <0.0001%BW |

SHERWIN INCORPORATED

Robert Siegel
Laboratory Director

