

**TEST REPORT**


Date: March 25, 2013

Company: Nawoo Tech Ltd

Test Report NP13

We hereby certify that samples of the material identified below by batch number, have been analyzed in accordance with test methods that meet and/or exceed the detection limits for fluoride, chloride, and sulfur per ASME Boiler and Pressure Vessel Code, Section V, Article 6, paragraph T-641, 1998-2011 Editions and Addenda with the following results:

<b>SAMPLE</b>		<b>RESIDUE</b>	<b>FLUORIDE</b>	<b>CHLORIDE</b>	<b>SULFUR</b>
<b>PICO COLOR CHECK PENETRANT BATCH NO.</b>	<b>NPP-2 13NPP14</b>	<b>21.9941 G</b>	<b>&lt;0.0001%BW</b>	<b>&lt;0.0002%BW</b>	<b>&lt;0.0002%BW</b>

**SHERWIN INCORPORATED****Robert Siegel  
Laboratory Director**