

## TEST REPORT

Date: March 20, 2005  
Lab #: T122005-1  
Company: Nawoo Tech Research Ltd

We hereby certify that samples of the material identified below by batch number, have been analyzed in accordance with test methods that meet and/or exceed the detection limits for fluoride, chloride, and sulfur per ASME Boiler and Pressure Vessel Code, Section V, Article 6, paragraph T-641, 1998 Edition, 2000 Addenda, 2001 Edition, 2002 and 2003 addenda, with the following results:

SAMPLE		RESIDUE	FLUORIDE	CHLORIDE	SULFUR
PICO COLOR CHECK PENETRANT BATCH NO.	NPP2 05NPP06	44.8264 G	<0.0001%BW	<0.0003%BW	<0.0003%BW

SHERWIN INCORPORATED



Robert Siegel  
Laboratory Director

