TEST REPORT

Date: March 13, 2008 Lab #: T22808-1

Company: Nawoo Tech Ltd

We hereby certify that samples of the material identified below by batch number, have been analyzed in accordance with test methods that meet and/or exceed the detection limits for fluoride, chloride, and sulfur per ASME Boiler and Pressure Vessel Code, Section V, Article 6, paragraph T-641, 1998-2006 Editions and Addenda with the following results:

SAMPLE

RESIDUE

FLUORIDE

CHLORIDE

SULFUR

PICO COLOR

NPP 2

2.4553 G

<0.0001%BW

<0.0002%BW

<0.0002%BW

CHECK PENETRANT

BATCH NO.

08NPP09

SHERWIN INCORPORATED

Robert Siegel

Laboratory Director

