

TEST REPORT

Date: April 14, 2009
Company: Nawoo Tech Ltd

We hereby certify that samples of the material identified below by batch number, have been analyzed in accordance with test methods that meet and/or exceed the detection limits for fluoride, chloride, and sulfur per ASME Boiler and Pressure Vessel Code, Section V, Article 6, paragraph T-641, 1998-2008 Editions and Addenda with the following results:

SAMPLE		RESIDUE	FLUORIDE	CHLORIDE	SULFUR
PICO COLOR CHECK PENETRANT BATCH NO.	NPP-2 09NPP10	4.9562 G	<0.0001%BW	<0.0022%BW	<0.0002%BW

SHERWIN INCORPORATED



Robert Siegel
Laboratory Director