

TEST REPORT

Date: March 12, 2012

Company: Nawoo Tech Ltd

We hereby certify that samples of the material identified below by batch number, have been analyzed in accordance with test methods that meet and/or exceed the detection limits for fluoride, chloride, and sulfur per ASME Boiler and Pressure Vessel Code, Section V, Article 6, paragraph T-641, 1998-2011 Editions and Addenda with the following results:

SAMPLE		RESIDUE	FLUORIDE	CHLORIDE	SULFUR
PICO COLOR CHECK PENETRANT BATCH NO.	NPP-2 12NPP13	7.1054 G	<0.0002%BW	<0.0002%BW	<0.0002%BW


SHERWIN INCORPORATED**Robert Siegel
Laboratory Director**