

TEST REPORT

Date: March 12, 2012

Company: Nawoo Tech Ltd

We hereby certify that samples of the material identified below by batch number, have been analyzed in accordance with test methods that meet and/or exceed the detection limits for fluoride, chloride, and sulfur per ASME Boiler and Pressure Vessel Code, Section V, Article 6, paragraph T-641, 1998-2011 Editions and Addenda with the following results:

SAMPLE		RESIDUE	FLUORIDE	CHLORIDE	SULFUR
PICO COLOR CHECK DEVELOPER BATCH NO.	NPD-4 12NPD13	12.8861 G	<0.0007%BW	<0.0035%BW	<0.0020%BW

SHERWIN INCORPORATED**Robert Siegel**
Laboratory Director